

ENG 2025-01: 2025 Resurfacing  
Project Information Sheet

**\*\*\* Pine Cove Heights Subdivision \*\*\***

**Beaver Run Road – 0.32 Miles – 22’ wide – Beginning at White Water Road Ending at Quail Nest Drive**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline and edge line stripe 4” wide – once after topping
- Permanent centerline and edge line stripe 5” wide – 15 days after topping
- 1 Stop Bar (24” Thermoplastic)

**Quail Nest Drive – 0.09 Miles – 22’ wide – Beginning at Beaver Run Road Ending at Twin Oaks Road**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline and edge line stripe 4” wide – once after topping
- Permanent centerline and edge line stripe 5” wide – 15 days after topping
- 2 Stop Bars (24” Thermoplastic)

**Twin Oaks Road – 0.31 Miles – 22’ wide – Beginning at White Water Road Ending at Quail Nest Drive**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline and edge line stripe 4” wide – once after topping
- Permanent centerline and edge line stripe 5” wide – 15 days after topping
- 1 Stop Bar (24” Thermoplastic)